

Tanner Facility Installation Specifications:

1. The Customer shall provide all digging, backfill, cleanup and restoration to County and applicable jurisdiction specification. Minimum trench depths are 42" for all trenches in public rights-of-way, 42" for primary in all locations, and 30" for secondary on private property, with sand bedding if required by Tanner.
2. The Customer shall obtain all easements on Tanner's easement form.
3. All meter bases and state-inspected wiring will be provided and installed by the Customer.
4. Center of all meter bases shall be between 60" and 72" from final grade.
5. Estimates are installed, and include material, labor, testing, energization, and all miscellaneous parts for a complete system.
6. Construction cannot begin until the Total Estimated Amount Due has been received at Tanner's office, all easements have been recorded, and permits procured.
7. Temporary service is provided by the Customer. Charge above includes connection of service wires to transformer.
8. Services cannot be energized until approved by the state inspector.
9. Estimates above include all applicable sales tax.
10. This estimate is valid for 90 days from the submission date.